

## **Test Monitoring Center**

@ Carnegie Mellon University 6555 Penn Avenue, Pittsburgh, PA 15206, USA

http://astmtmc.cmu.edu 412-365-1000

Sequence VIII Information Letter 14-2 Sequence No. 16 June 30, 2014

TO: Sequence VIII Mailing List

SUBJECT: Correction of Typographical Errors

Recently the Sequence VIII Surveillance Panel, via electronic ballot, agreed to address typographical errors noted in Sections 11.1.7.2 and 11.1.7.3. Section 11.1.7.2 has been revised to reflect a 4 hour time limit and section 11.1.7.3 has been revised to reflect a 4 hour time limit and to reference section 11.1.7.1 rather than 11.1.7.

These changes are effective with the issuance of this letter.

Fred Gerhart Chairman,

Sequence VIII Surveillance Panel

Bush Derbart

Frank M. Farber

Director

**ASTM Test Monitoring Center** 

Frank m Failer

Attachment

c: ftp://ftp.astmtmc.cmu.edu/docs/gas/sequenceviii/procedure\_and\_ils/il14-2-16.pdf

Distribution: Email

## (Revises Test Method D6709-13 as amended by Information Letter 14-1)

- 11.1.7.2 During the shutdown between the 4 h run-in and 0.5 h flush, consider any time in excess of 85 min as off-test time counted against the 4 h limit listed in 11.1.7.1.
- 11.1.7.3 During the shutdown after the 0.5 h flush, consider any time in excess of 145 min as off-test time counted against the 4 h limit listed in 11.1.7.1.